

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/21/06

CORNER DESIGNATION: 3N31, X-9, The East One-Quarter Corner of Section 32.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

State Highway Department freeway right-of-way and monumentation maps for Interstate 84 show a state plane coordinate (NAD 1927) for this corner. The maps do not indicate what was recovered.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T3N R31E  
1  
4  
S32|S33  
2006  
PLS 1106

**MONUMENT SET:**

Re-established corner using indexed Oregon State Highway Department freeway map coordinates, after indexing State coordinates to our State Plane measurement values at freeway centerline monuments at 930+94.45 and 985+59.60. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with top flush with ground surface.

From which:

A 3/4" brass washer 1 foot above ground level in UECA pole No. 333401 bears North 83° East, 6.0 feet. Attached witness post sign to pole.

A blue Deep-1 magnet buried 24" in ground bears South 30 1/2° East, 46.3 feet.

A purple Deep-1 magnet buried 24" in ground bears South 48 1/2° West, 38.7 feet.

An orange Deep-1 magnet buried 24" in ground bears North 38° West, 39.1 feet.

Attached bearing object sign to UECA pole and buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located at the end of a field road running North. A UECA power pole line runs North-South through the corner area. There is a field line extending West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 744047.80

E = 8597101.98

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/3N31X9

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1927  
WILLIAM R. WELLS  
1106

*renews 6-30-08*

*01-11-08*