

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/21/06

CORNER DESIGNATION: 3N31, Z-11, The South One-Quarter Corner of Section 33.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N
R31E
1 S33
4 S4
T2N
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure on parallel of latitude holding the recovered or reestablished Southwest and Southeast corners of Section 33. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 20" galvanized iron pipe with cap 6" below gravel road surface.

From which:

A 5/8" x 30" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 53° East, 39.5 feet.

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 52 1/2° East, 35.3 feet.

The center at ground level of a telephone pedestal bears South 69 1/2° West, 51.7 feet.

A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in UECA pole No. 335000 bears North 14° West, 29.6 feet. Attached witness sign to pole.

Attached bearing object sign to UECA pole and iron rebar accessories.

LOCATION AND COMMENTS: Corner is located approximately 4 feet South of the Centerline of Fransier County Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 741396.96

E = 8599781.41

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31Z11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08