

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/17/13

CORNER DESIGNATION: 3N32, C17, The West One-Quarter Corner of Section 2.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for 1/4 Sec. corner in mound of Earth with charred stake, pits, trench &c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E  
1/4  
S3|S2  
2013  
PLS 54657

MONUMENT SET: Held the line between the Southwest and Northwest corners of Section 2 at it's intersection with a East-West field berm as best remaining evidence of the original corner location and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, marked as shown in "Monument Marking Detail", from which:

A silver deep-1 magnet, buried 20" in the ground, bears North 45° East, 41.6 feet.

A pink deep-1 magnet, buried 20" in the ground, bears South 54° East, 40.8 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 45° West, 28.3 feet.

An orange deep-1 magnet, buried 20" in the ground, bears North 56 1/2° West, 36.2 feet.

Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner located in an East-West field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 770959.63'

E= 8639236.23'

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

Dean Roy

\3N32C17

