

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/19/13

CORNER DESIGNATION: 3N32, E09, The Northwest Corner of Section 9.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for corner to secs 4, 5, 8 & 9 in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E  
S5 | S4  
S8 | S9  
2013  
PLS 54657

MONUMENT SET: The corner point falls in farmed fields with no features. I calculated the position for the corner point by double proportion measure holding the West one-quarter corner of Section 4 and an East-West field berm near the East one-quarter corner of Section 8 for latitude and the Northeast corner of Section 9 and North one-quarter corner of Section 8 for departure. The Chaplin record was used in proportioning. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground in farmed field, marked as shown in "Monument Marking Detail", from which:

- A silver deep-1 magnet, buried 20" in the ground, bears North 44 1/2° East, 40.3 feet.
  - A pink deep-1 magnet, buried 20" in the ground, bears South 41° East, 47.6 feet.
  - A blue deep-1 magnet, buried 20" in the ground, bears South 24 1/2° West, 40.6 feet.
  - An orange deep-1 magnet, buried 20" in the ground, bears North 47° West, 33.0 feet.
- Buried bearing object tags with magnets.

LOCATION AND COMMENTS: In farmed field, no features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 768113.82'  
E= 8628719.34'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

\3N32E09



RENEWS: 6-30-14