

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 3N, R 32E., W.M.

Corner Code No. G-13

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by David Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated August 21, 1864. The original notes state that at the corner a wood post with charred stake, earth mound and pits was set for the corner.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Intersection of State Highway No. 37 and gravel road running east. An old locust post was found at the beginning of the field line between fields extending to the west. The locust post is a remnant of the old east-west fence which used to exist in this area.

Description of monument and accessories I established to perpetuate the original location of this corner:

After surveying to improvements and existing features such as field lines and road intersections located north, south and west of the corner position, and finding the new measurements matching the record survey measurements closely, I accept the intersection of centerline of State Highway No. 37, together with the line between the locust post to the west and the gravel road to the east as the best remaining evidence of the corner location (See recorded survey map).

At the corner point I set a 2 1/2" by 12" aluminum pipe with 2 1/2" aluminum cap, in a monument box consisting of a 15" pvc pipe sleeve and monument access cover, in the pavement of State Highway No. 37, and surrounded the monument with mortar.

Referenced the monument as follows. From the new monument:

An aluminum nail in the south side of PP&L pole no. 100501 bears N62°E 31.57'. The aluminum nail is about 1' above the ground. Attached witness corner and bearing object signs to the pole.

An aluminum nail in the south side of PP&L pole no. 100502 bears N76°E 53.95'. The aluminum nail is about 1' above ground.

The centerline of a phone pedestal bears N84°W 28.4'. The measurement was made to the phone pedestal at ground level.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Survey Dept County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 6th day of May, 1988
David H. Keambin by William R. Wells
(COUNTY OFFICIAL) (DEPUTY)