

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/31/13

CORNER DESIGNATION: 3N32, G21, The East One-Quarter Corner of Section 11.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of earth with charred stake pits & as per instructions

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1/4
S11|S12
2013
PLS 54657

MONUMENT SET: Corner point falls in road with no features to control corner latitude. Reestablished corner position by single proportion measure between the Southeast and Northeast corners of Section 11 using the Chaplin Record. At reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 12 inches below road surface, stamped as stated in "Monument Marking Detail", from which:
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657", in road bank, bears North 21 1/2° East, 31.8 feet.
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657", in road bank, bears South 22° East, 32.1 feet.
A blue deep-1 magnet buried 20" below ground surface in farmed field bears South 56° West, 30.6 feet.
An orange deep-1 magnet buried 20" below ground surface in farmed field bears North 44° West, 41.5 feet.
Attached bearing object signs to all accessories.

LOCATION AND COMMENTS: Located just East of the centerline of Campbell Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N= 765794.18'
E= 8644652.39'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
\\3N32G21

