

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/21/13

CORNER DESIGNATION: 3N32, J03, The North One-Quarter Corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions. In undated Survey No. Q-521-C, F.B. Hayes states he set a "1" I.P." for the corner point.

MONUMENT AND ACCESSORIES FOUND: Found 1 1/2" square bar buried 14" deep near the edge of a farmed field. This monument is believed to be the 1" I.P. set by Hayes in Survey No. Q-521-C.

MONUMENT MARKING DETAIL:

MONUMENT SET: I did not remonument the bar because it is firmly set below ground. From found bar:

- A silver deep-1 magnet, buried 20" in the ground, bears North 12° East, 37.7 feet.
- A 3/4" brass washer stamped "PLS 1106", in fence post, bears South 66° East, 67.5 feet.
- A 3/4" brass washer stamped "PLS 1106", in fence post, bears South 12° West, 89.6 feet.
- An orange deep-1 magnet, buried 20" in the ground, bears North 67° West, 42.1 feet.
- Buried bearing object tags with magnets and attached witness post signs to fence posts.

LOCATION AND COMMENTS: Corner is located at projection of fence line East and Road to the South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 762701.00'  
E= 8620897.92'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

\3N32J03

