

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/13/13

CORNER DESIGNATION: 3N32, L05, The West One-Quarter Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions. F.B. Hayes shows this corner on his undated Survey No. Q-521-C but does not note anything found or set.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1/4
S18 | S17
2013
PLS 54657

MONUMENT SET: Reestablished corner position by single proportion measure between the Southeast and Northeast corners of Section 18 and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, marked as shown in "Monument Marking Detail", from which:

A silver deep-1 magnet, buried 20" in ground, bears North 36° East, 35.9 feet.

A 3/4" brass washer stamped "PLS 1106" on PP&L pole #189401, bears South 04 1/2° West, 326.1 feet.

A 3/4" brass washer stamped "PLS 1106" on PP&L pole #189502, bears North 56° West, 37.6 feet.

A 3/4" brass washer stamped "PLS 1106" on PP&L pole #189501, bears North 04° West, 389.4 feet.

Attached bearing object tags on all magnets.

LOCATION AND COMMENTS: Corner is located 25 feet East of a North-South line of PP&L power poles.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 760096.96'
E= 8623575.89'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
\\3N32L05

