

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/05/04

CORNER DESIGNATION: N-11, The South One-Quarter Corner of Section 21, Township 3 North, Range 32 East, W.M., Umatilla County, Oregon.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by David P. Thompson, under GLO Contract No. 106, dated August 16, 1864. Record states: Set post for 1/4 Sec. corner in mound of Earth with charred stake, pits &c as per instructions. An undated, hand written sketch found in County Survey office files, notes "stone 16 x 8 x 6" at corner point. I suspect this sketch is from old Hayes and Harris files.

MONUMENT AND ACCESSORIES FOUND: Accepted position on lone wood fence post in East-West field line as best remaining evidence of original corner point. County Road No. 353, now vacated, formerly passed East-West through the corner point.

**MONUMENT MARKING DETAIL:**

T3N R32E  
1 S16  
4 S21  
2004  
PLS 1106

**MONUMENT SET:**

At a point 0.3' East of the East edge of lone wood post in East-West field line, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 14" below ground level. Cap is marked as shown in "Monument Marking Detail".

**New Accessories:**

- A silver deep-1 magnet buried 20" in ground bears N 43° E, 25.8 feet.
- A purple deep-1 magnet buried 20" in ground bears S 46° E, 29.8 feet.
- A blue deep-1 magnet buried 20" in ground bears S 48° W, 32.7 feet.
- An orange deep-1 magnet buried 20" in ground bears N 50° W, 27.9 feet.
- Buried bearing object tags with all deep-1 magnet accessories.
- Attached "witness" sign to locust fence post near brass cap monument.

LOCATION AND COMMENTS: Corner is located in active wheat field.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Marc Hammersla  
3N32N11

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-04*