

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/31/13

CORNER DESIGNATION: 3N32, N05, The Southwest Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for corner to Secs 17, 18, 19 & 20 in mound of earth with charred stake pits & as per instructions. F.B. Hayes, in undated Survey No. Q-521-C, states "Marked Stone Found". Umatilla County Survey 12-126-B, by JUB Engineers, Inc., states: "Calculated corner. Corner obliterated, held the intersection of the centerline of Howdysshell Road (Co. Rd. 1096) to the East and the centerline of Hagen Road (Co. Rd. 1087) to the South. No monument found or set in this survey."

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
S18|S17
S19|S20
2013
PLS 54657

MONUMENT SET: Held corner position as determined by Survey No. 12-126-B. Located position by ties to monuments set on Survey No. 12-126-B. Reestablished corner by setting a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 8 inches below road surface, stamped as stated in "Monument Marking Detail", from which:
A 3/4" brass washer stamped "PLS 1106" in PP&L power pole #170001 bears North 75° East, 72.7 feet.
A 3/4" brass washer stamped "PLS 1106" in PP&L power pole # 200900 bears South 18 1/2° East, 49.1 feet.
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657" in road bank bears North 76° West, 53.8 feet.
A 3/4" brass washer stamped "PLS 1106" in PP&L power pole #170000 bears North 04° West, 49.7 feet.
Attached bearing object signs to all accessories.

LOCATION AND COMMENTS: Located at a road intersection, Howdysshell, East-West, and Hagen North-South. Monument is near the North edge of Howdysshell Road gravel.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 757464.72'
E= 8623614.60'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East
Witnesses: Jason Wells, PLS
Dean Roy

Surveyor's Seal

√2N32N5



RENEWS: 6-30-14