

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/30/13

CORNER DESIGNATION: 3N32, T21, The East One-Quarter Corner of Section 26.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of earth with charred stake pits & as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1/4
S26|S25
2013
PLS 54657

MONUMENT SET: Reestablished the corner by single proportion measurement between the Northeast and Southeast corners of Section 26. At the reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 12" below ground, stamped as stated in "Monument Marking Detail", from which:

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap marked "Wells Surveying PLS 54657" on road bank in fence line bears North 38 1/2° East, 30.5 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap marked "Wells Surveying PLS 54657" on road bank in fence line bears South 42° East, 27.5 feet.

A blue deep-1 magnet buried 22 inches below ground level in road bank bears South 39° West, 25.8 feet.

An orange deep-1 magnet buried 22 inches below ground level in road bank bears North 42° West, 24.9 feet.

Buried bearing object signs with magnets.

Attached bearing object signs to rebar.

LOCATION AND COMMENTS: Corner located just East of the West edge of Campbell Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 749957.79'
E= 8644959.42'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
/3N32T21

