

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/30/13

CORNER DESIGNATION: 3N32, V11, The North One-Quarter Corner of Section 33.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions. Corner position was computed by single proportion by Stephen Haddock, 10/2006, Survey No. 06-606-C, record states: "Corner point calculated following the 1973 BLM manual of instructions. Nothing found or set."

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1 S28
4 S33
2013
PLS 54657

MONUMENT SET: Held a point 1 foot North of 6" diameter fence corner post with fence South and field berms North, South and East as best remaining evidence of the original corner position and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top flush with ground marked as shown in "Monument Marking Detail", from which:

- A silver deep-1 magnet, buried 20" in the ground, bears North 33° East, 41.2 feet.
 - A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657", bears South 02° West, 31.8 feet.
 - A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657", bears South 01° West, 63.8 feet.
 - An orange deep-1 magnet, buried 20" in the ground, bears North 49° West, 38.3 feet.
- Buried bearing object tags with magnets. Attached witness post sign to fence post near monument.

LOCATION AND COMMENTS: Located 1 foot North of 6" diameter fence corner post with fence South and field berms North, South and East, in farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N= 747066.67'
E= 8631816.02'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
3N32V07

