

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. A-21

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by D. Thomsen, U.S. Deputy Surveyor, under Contract No. 106, dated August 16, 1864. The original notes state that at the corner a wood post, with charred stake, earth mound and pits was set for the corner.

Record of Private Surveys, Book 1, located in the County Surveyor's Office at page 318, shows a statement by John Kimbrell, that he made surveys and set corners for Section 2 and Section 1 as shown on page 310. Page 310 shows a measurement of 80.09 chains for the north line of Section 2, so apparently Kimbrell had recovered this corner prior to 1895.

The next reference for this corner is shown on Map G-1121-B, where Wayne Harris states that an unmarked brass cap was found.

The other reference to this corner was found on Map No. R-23-B, where Terry Hanby states that he found a brass cap.

Contacts of area surveyors did not disclose any information which shows how or when the monument was set. The monument is stamped by Dave Krumbein, PLS 933.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found and accepted the position of a 2 1/2" brass cap on a 1 1/2" by 36" galv. iron pipe. This monument was found near a fence corner, the fence goes south from the monument. The top 1' of the monument was bent over but the bottom 2' of the monument was straight and the corner position was determined at the position of the straight part of the monument.

The found monument is marked as follows:

UMATILLA COUNTY
 T3N R32E
 S35 | S36
 S2 | S1
 T2N R32E
 PLS 933
 SURVEYOR

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the found monument, I set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe 30" in the ground. Buried the old monument alongside the new monument underground. Established reference monuments as follows. From the new monument:

An aluminum nail in the north side of a cut off power pole 4' high bears N50°W 1.12'. Attached witness corner and bearing object sign to the pole.

A 1 1/2" aluminum cap, marked as shown, set on a 5/8" by 30" iron rod bears S3°W 25.01'. Set steel fence post next to reference monument and attached witness corner and bearing object sign.

The aluminum cap on the reference monument is marked as follows:

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106



Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)