

OREGON CORNER RESTORATION FORM

Section: 1, 2, 11, 12 Township: 3N Range: 33E
County: Umatilla Date: 2/14/2011

Corner Designation: 3N33E21

Section corner common to Sections 1, 2, 11, 12, T3NR33E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally surveyed by Chaplin in 1864. He set a post in a mound of earth.
In 1976 Krumbein set a brass cap in Survey M-121-C.

Monuments and Accessories Found: (Condition and Source):

- A 2 1/2" brass cap, 7" below the road surface.
- A 2 1/2" brass cap witness corner lies S1° 45' E, 19.50'.
- A 2 1/2" brass cap witness corner lies N 5° 20' W, 17.65'.

Diagram



ORANGE
MAGNET •

DEINING RD.

Sketch

○ BC WC

○ BC

○ BC WC

○ PPL
IR •

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N769104.70
E8676240.08

Monument(s) Set (Procedures and Description):

None.

References Set:

- "Deep One" magnet by Bermtsen.
- An orange magnet lies N 68° 45' W, 40.02', 1.0' deep.
- A 5/8" x 30" iron rebar w/RPC #43406 lies S 83° E, 113.21', at a power pole.

Location and Comments:

The corner is 1/2 mile East of the intersection of the Helix Hwy. and Deining Rd.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English

OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Firm / Agency

Date: 7/10/2012
Rec'd By: J. Res
No. 12-094-C

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/13