

**OREGON CORNER RESTORATION FORM**

Section: 1, 12  
County: Umatilla

Township: 3N  
Date: 3/23/2011

Range: 33E

Corner Designation: 3N33E23 (Amended 4/2/2012)

Quarter corner common to Sections 1, 12, T3NR33E.


_____	Condition Report Only
_____ X	Not Found
_____ X	Remonumented
_____	Unrecorded
_____ X	Surveyed In
_____ X	Referenced Out

**Previous Renewals / Surveys, etc.**

Originally surveyed by Chaplin in 1864. He set a post in a mound of earth.

**Monuments and Accessories Found: (Condition and Source):**  
None.

Diagram



Sketch

ORANGE  
MAGNET

SILVER  
MAGNET

DEINING RD.

O BC

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N769182.97  
E8678842.99

BLUE  
MAGNET

PINK  
MAGNET

**Monument(s) Set (Procedures and Description):**

A 1 1/8" x 30" galvanized iron pipe with a 2 1/2" brass cap, stamped as shown above, 1.0' below the surface. The corner location was reestablished by using the single proportionate method between found monuments to the East and West.

**References Set:**

- "Deep One" magnets by Berntsen.
- An orange magnet lies N35° 50' W, 22.88', 1.5' deep.
- A silver magnet lies N 24° 50' E, 24.26', 1.6' deep.
- A pink magnet lies S 50° 10' E, 22.05', 1.6' deep.
- A blue magnet lies S 44° 20' W, 19.40', 1.6' deep.

**Location and Comments:**

The corner is located 1 mile East of the intersection of Deining Rd. and the Helix Hwy.

**Compass Declination**  
17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

**Firm / Agency**

Date: 2/10/2012  
Rec'd By: S. [Signature]  
No. 12-094-C

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/13