

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/29/01

CORNER DESIGNATION: A-25, Northeast Corner of Section 1, Township 2 North, Range 33 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by David P. Thompson, under Contract No. 106, dated Aug. 16, 1864. Record states: Set post for corner to Townships 2 & 3, North Ranges 33 & 34 East in mound of earth with charred stake, pits, trench & c., as per instructions. Corner re-established by Z.F. Moody, under contract No. 145, dated April 23, 1871. Record states: Set post and made mound of earth for cor. to Tps. 2 & 3 North Ranges 33 & 34, East. Corner recovered by Currin and Noland, under contract dated May 4, 1887. Record states: Intersect N. boundary 35 lks. W. of Corner to Ts. 2 & 3, N. Rs. 33 & 34 E.. Corner was recovered and remonumented by C.E. Redfield, U.S. Indian Service Surveyor, March 7, 1918. Notes state: N 0° 16' E bet. 1 & 6, and at 76.49 chains, Pt. for Tp. Cor. bears West 17 lks. Redfield's notes are vague as to how the corner was remonumented.

MONUMENT AND ACCESSORIES FOUND: Found 2" galvanized iron pipe bent, 6" below ground with no brass cap. This is a Redfield monument damaged by farming.

## MONUMENT MARKING DETAIL:

T3N  
R33E S36|S31 R34E  
S1|S6  
T2N  
2001  
PLS 1106

## MONUMENT SET:

At position of found Redfield monument, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe with top buried 20" below ground. Removed 2" galvanized iron pipe as it is in the way of new monument. Monument marked as shown in Monument Marking Detail.

## New Accessories:

An orange deep-1 magnet, buried 20" in the ground, bears N 30° E, 24.1 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", set flush with ground bears S 04° E, 46.0 feet.

A blue deep-1 magnet buried 24" in the ground, S 51° W, 68.5 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap buried 18" below the ground, bears N 43° W, 25.5 feet.

Buried bearing object signs alongside all deep-1 magnets and attached bearing object signs to rebar accessories.

## LOCATION AND COMMENTS:

Corner falls in field just North of road corner (roads South and East) in line with field lines North and West.

STATE PLANE CO-ORDINATE, Oregon North, NAD 83/91, International Foot:

N= 742748.83

E= 8682080.16

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Mark Hammersla

V2N33A25

RECEIVED BY  
Umatilla County Surveyor  
Date 12-01  
Rec'd By KF  
Sta. 01-212-R

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-01*