

OREGON CORNER RESTORATION FORM

Section: 12, 13, 7, 18
County: Umatilla

Township: 3N
Date: 3/7/2012

Range: 33E, 34E

Corner Designation: 3N33J25

Section corner common to Sections 12, 13, T3NR33E; 7, 18, T3NR34E.

	Condition Report Only
X	Not Found
X	Remonumented
	Unrecorded
X	Surveyed In
X	Referenced Out


Previous Renewals / Surveys, etc.

Originally surveyed by Thompson in 1864. He set a post in a mound of earth, with charred stake, pits, and trench. In 1885 Zahner found the corner in an unnumbered Private Survey, as recorded in Book 1, pp. 98-99.

Monuments and Accessories Found: (Condition and Source):

None.

Diagram



Sketch

ORANGE
MAGNET ●

SILVER
MAGNET ●

○
BC

BLUE
MAGNET ●

PINK
MAGNET ●

FIELD ROAD

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N763994.12
E8681599.19

Monument(s) Set (Procedures and Description):

A 1 1/8" x 30" galvanized iron pipe with 2 1/2" brass cap, stamped as shown above, 1.5' below the surface. The corner location was reestablished by holding the centerline of the North-South field road for Easting and single proportioning back from the Northeast corner of Section 12 to the East-West fence line at the quarter corner common to Section 12, T3NR33E and Section 7, T3NR34E to establish the Northing.

References Set:

- "Deep One" magnets by Berntsen.
- An orange magnet lies N 46° 20' W, 36.67', 1.7' deep.
- A silver magnet lies N 48° E, 31.00', 1.7' deep.
- A pink magnet lies S 49° E, 31.53', 1.7' deep.
- A blue magnet lies S 47° 40' W, 32.43', 1.8' deep.

Location and Comments:

The corner is located 1 mile West-Northwest of the intersection of Adams Rd. and Rothrock Rd., in a field road.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English

OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RENEWAL DATE: 12/31/13

RECEIVED BY:

Date: 7/10/2012
Rec'd By: S. Pres
No. 12-094-C

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055