

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/15/15

CORNER DESIGNATION: N-9, The Northeast Corner of Section 20, Township 3 North, Range 35 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Zenas F. Moody, under contract dated October 4, 1871. Notes State: Set a post and made mound of earth for corner to sections 20, 21, 16, and 17. Currin and Noland under special contract dated May 4, 1887, state they started at "the corner" and intersected "the corner" but do not say what "the corner" is. Record of private survey No. 96 and 328 by Kimbrell also state "the corner" but do not say what the corner is. All subsequent surveys are thought to have found Moodys section corner post.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in a farmed field. Proportioned departure against Kimbrells Record of Surveys No. 96 and 328. See Property Line Adjustment Survey map filed concurrently with this certificate for further details.

MONUMENT MARKING DETAIL:

T3N R35E
S17|S16
S20|S21
2015
PLS 54657

MONUMENT SET: At the corner point set a 2" aluminum cap on 5/8"x30" rebar with the top of the cap 22" below ground level. Because of several larger rocks and hard pan soil, a brass cap and iron pipe monument would not be set deep enough to not get farmed out. Monument marked as shown in "Monument Marking Detail".

From which:

The West 1/16th corner of Sections 16/21 (set on survey filed concurrently with this certificate), a 5/8"x30" iron rebar with 1 1/4" blue plastic cap marked "Wells Surveying PLS 54657" buried 22" below ground level in farmed field bears North 89° 48' 13" East, 1331.27 feet.

A 5/8"x24" iron rebar with 1 1/4" blue plastic cap marked "Wells Surveying PLS 54657" 2" above ground level in unfarmed scab area, on East side of a large rock dump near the Southeast corner of and old concrete building foundation bears GRID AZIMUTH 216°56', 50.1 feet.

A 5/8"x24" iron rebar with 1 1/4" blue plastic cap marked "Wells Surveying PLS 54657" 2" above ground level in unfarmed scab area, on South side of small drainage ditch bears GRID AZIMUTH 316°19', 58.8 feet.

A 5/8"x30" iron rebar with 1 1/4" blue plastic cap marked "Wells Surveying PLS 54657" buried 22" below ground, set for a point on the North line of the Northeast 1/4 of Section 20 (set on survey filed concurrently with this certificate), bears South 89°48'13" West, a distance of 2640.05 feet.

Wired bearing object signs to both rebar accessories near corner monument.

LOCATION AND COMMENTS: Corner is located in a farmed field. See Survey Map filed concurrently with this certificate.


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

/3N35N9

16-011-C



RENEWS: 6:30:16