

CEA¹ED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. Z-1


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1865. The original notes state that at the corner a wood post was set.

In 1889, during his County Survey No. 46, Surveyor Arnold recovered and re-monumented the corner as follows:

"Int. S. bndy. of Tp. 73 ft. west of Tp. cor., which is the old original post, lying on an old ad. with pits, and a basalt stone, wkd. 3 notches N, S, E. and W. and + on top, on S.E. hill side, in apple of ravine run g. S into Pine creek, about 500 ft. N.W. of Junction. I measure said stone, 24 by 12 by 7 ins., and cut 6 notches on N, and on S., faces, and 6 notches on E., and on W. edges, and reset same in ad."



Corner No.
Compass Declination 19.0°

Description of corner evidence found:

24" by 12" by 7" basalt stone, at the north side of a fence corner with fences going Southeast, West and South, marked with 6 notches on North, South, East and West edges.

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the found stone, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 24" in the ground and surrounded with a mound of earth and stone. Buried marked stone in the new mound. Set reference monuments as follows:

A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron rod bears N78°W 20.5'. Placed bearing object sign on wood fence post by R.M.. A 1 1/2" alum. cap, marked as shown below, set on a 5/8" by 30" iron pipe, bears S78°E 17.9'. Set steel fence post next to reference monument and attached bearing object sign.

Set steel fence post East of corner and attached witness corner sign.

The alum. cap on the reference monument is marked:

R M
17.9 Ft.
←
Sec 6
1106

Note: There is 12° to 15° degrees of westerly local magnetic attraction in the corner vicinity. Bearings to reference monuments do not take into account the local attraction.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Survey County of Umatilla 7-27-88
State of OR I hereby certify that the within instrument was filed in this office
for record on the 27th day of July, 1988
David H. Humbert by William R. Wells
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 7-88

Rec'd By WA

No. 88-42-C