

CLASSIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.


Corner Code No. Z-7

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1865. The original notes state that at the corner a wood post was set from which:

- A 8" larch bears N75°E 59 lks.
- A 12" fir bears S78°W 42 lks.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

A 18" western larch snag, 20' high, with scribes "BT" visible after opening the lower blaze, bears N75°E 38.9 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At a point S75°W 38.9 feet from the found bearing tree, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 14" in the ground to bedrock and surrounded with a mound of earth and stone from which:

- A 11" douglas fir bears N77°E 29.5' scribed 1/4 S32 BT.
- A 15" douglas fir bears S40°E 41.3' scribed 1/4 S5 BT.

Attached bearing object signs to each of the bearing trees and set a steel fence post west of corner with a witness corner sign attached.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Sudney County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July, 1988
David H. Lambson by William R. Wells
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 7-88

Rec'd By JA

No. 88-42-C