


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-17  
T3N, R36E

1/4 CORNER TO SECTIONS 22 AND 23, T 3N, R36E, WM.

History of original corner establishment:

ESTABLISHED BY G.S. PERSHIN UNDER HIS CONTRACT No. 305, DATED MAY 4, 1878. HIS NOTES READ AS FOLLOWS:  
SET STONE, 17x10x6 ON STEEP SOUTH HILLSIDE FOR 1/4 SEC. COR.  
FROM WHICH: A PINE, 18" DIAM. BR. N5°E, 130 LKS. DIST.



Description of corner evidence found:

FOUND OBT, 30" PINE, PARTLY OPEN FACE WITH SCRIBES "1/4 S BT" VISIBLE, BEARS N 5°E, 130 LKS. (= 85.8 FT.)


I DID NOT FIND KRUMBEIN'S BRASS CAP, SHOWN ON HIS SURVEY FOR DOUG SPROED, C.S. FILE No. 83-81-B.

Description of monument and accessories established to perpetuate the original location of this corner:

AT RECORD BEARING AND DIST. FROM FOUND OBT., I SET A 2"x30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN, 15" IN GROUND, IN A LARGE MOUND OF STONE

FROM WHICH:

MY NEW B.T., A 15" PINE, SCRIBED "1/4 S 22 BT" BEARS N 63°W, 133.2 FT.



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Victor M. McLeod*

OREGON  
JULY 17, 1970  
VICTOR M. MCLIND  
934

RECEIVED BY

Umatilla County Surveyor

Date 7-8-86

Rec'd By KA

No. 86-83-M  
(86-37-B)

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)