

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-21
T3N, R36E

1/4 CORNER TO SECTIONS 23 & 24, T3N R36E

History of original corner establishment:


ESTABLISHED BY G. S. PERSHIN UNDER HIS CONTRACT
No. 305, DATED SEPT. 20, 1878. HIS NOTES READ AS
FOLLOWS:

SET FIR POST ON EAST SIDE OF RIDGE FOR 1/4 SEC. COR.

FROM WHICH:

A FIR, 8 IN DIAM. BRS. N. 10° E. 52 LKS. DIST.

A FIR, 10 IN DIAM. BRS. N. 22° W. 60 LKS. DIST.



Description of corner evidence found:

NO EVIDENCE FOUND


Description of monument and accessories | established to perpetuate the original location of this corner:

AT PROPORTIONAL DISTANCE BETWEEN SECTION CORNERS
I SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP,
MARKED AS SHOWN, 24" IN GROUND.

FROM WHICH MY NEW BT'S:

A 6" FIR, SCRIBED "1/4 S 23 BT" BEARS S 10 1/4° W, 47.5 FT.

A 6 1/2" LARCH, SCRIBED "1/4 S 24 BT" BEARS S 40° E, 44.3 FT.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLeod

OREGON
JULY 17, 1970
VICTOR M. McLEOD
934

RECEIVED BY

Umatilla County Surveyor

Date 7-8-86

Rec'd By KA

No. 86-80-M

Ref. 86-37-B

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)