


LAND CORNER RECORD

LL 5680-2

1. T 3 N R 36 E No. T 13 Cor. 1/4 Mer. Will. State Oregon (Rectangular) N. F. Umatilla Dist. Pendleton 9

2. Corner Status

3. Original Description _____ Vol. _____ Page 34 Where Recorded GLO year 1878

4. Description of Corners:

Set stone 18x12x7 in creek bottom for 1/4 section corner, from which:
 Fir 8 inches diameter bears S 10° E 30 links distant
 Fir 6 inches diameter bears S 46° W 6 links distant.

5. Investigation Notes:

Using USGS notes and aerial photos as guide, we left the Umatilla River road, traveled approx. 1 mile south up Ryan Creek to search area indicated by photo. Found pile of rock, 18 x 12 x 7, 6-7" above ground in fair condition. No markings. From pile of rock a 26" fir bears S 46° W 32 links, 32" fir bears S 27° W 35 links. Old blazes grew over.

Placed B.T. signs on both firs. *Don't agree with original notes.*

The best way to reach corner is go up Ryan Creek for approx. 1 mile, the 1/4 corner is on east of travel, mound of stone is painted with silver paint. Orange ribbon tied on two fir B.T.S.

7. Photo Identification UM-7-17-64Photo No. Roll 29# 29-26Ident. By J. BerlinA. Galbraith 4/27/64

8. Plane Coordinate Position Data

State _____ Zone _____

X _____

Y _____

Estab. By _____

Field Book No. _____

Where Filed _____

9. Evaluation

Authentic _____

Needs Verif. Monument NoRe-estab. X Survey

Land Status _____

6. Signed A. Galbraith Title Range Technician Date 5-19-64

PERPETUATION RECORD

10. Monument:

11. Accessories

Field Book _____ Page _____

12. Set By _____ Title _____
License _____ Agency _____ Date _____

13. Recorded By _____ Volume _____ Page _____
(Agency)
(Date) (City) (County) (State)

14. Remarks:

T-13