


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by George S. Pershin under G.L.O. contract number 304 dated Sept., 19, 1878.

Surveyor General's records state:

Set a fir post 6" square 6' long on nearly level for cor to townships 3 & 4 N, ranges 37 & 38 E., W.M. from which:



- A fir 38" diam. bears N 58° E., 55 lks dist marked T 4 N R 38 E S 31 BT
- A fir 24" diam. bears S 76° E., 110 lks dist marked T 3 N R 38 E S 6 BT
- A fir 30" diam. bears S 33° W., 93 lks dist marked T 3 N R 37 E S 1 BT
- A fir 32" diam. bears N 45° W., 74 lks dist marked T 4 N R 37 E S 36 BT

Description of corner evidence found:

Found a 2 1/2" brass cap on a 2" iron pipe 8" above the ground

A fir snag 42" diam. bears S 76° E., 72.6 ft.(110 lks) dist. with R 38 E S 6 visible inside 8" of overgrowth.

A fir snag 42" diam. bears N 44° W., 48.8 ft.(74 lks) dist. with no visible scribe marks.

(No record of corner remonumentation in county files)

Description of monument and accessories established to perpetuate the original location of this corner

Placed sign 54-3 on sec 6 and sec 36 BT snags.



Office of.....Surveyor..... County of.....Umatilla.....
 State of...Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976.....
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)