


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

B-23

C-N 1/8 Cor. Sec. 1, T3N R37E

History of original corner establishment:

No Record



B-23

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" X 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 24" IN GROUND, FROM WHICH:

A PINE, 11" DIAM., SCRIBED "CN 1/8 S1 BT" BEARS S 71 1/4° E, 71.8 FT.

A PINE, 6" DIAM., SCRIBED "CN 1/8 S1 BT" BEARS S 7° E, 66.3 FT.

SET A STEEL POST 3' S. OF CORNER, WITH SIGN 54-4.

PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Victor M. McLind

OREGON  
JULY 17, 1970  
VICTOR M. MCLIND  
934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By RA

No. 86-93-R

Office of... SURVEYOR... County of... UMATILLA...

State of... OREGON... I hereby certify that the within instrument was filed in this office for record on the... day of... 19...

... by ... (COUNTY OFFICIAL) (DEPUTY)