


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N.E. 1/6 Cor. Sec. 1, T3N, R37E

History of original corner establishment:

No RECORD



B-24

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 24" IN GROUND, FROM WHICH:

- A FIR, 8" DIAM., SCRIBED "NE 1/6 S1 BT" BEARS N 36 1/2° W, 10.5 FT.
- A FIR, 10" DIAM., SCRIBED "NE 1/6 S1 BT" BEARS S 12 1/4° W, 15.8 FT.

SET A STEEL POST 3' S. OF CORNER, WITH SIGN 54-4.

PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED PROFESSIONAL LAND SURVEYOR

Victor M. McKind

OREGON JULY 17, 1970 VICTOR M. MCLIND 934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By [Signature]

No. 86-94-R

Office of... SURVEYOR... County of... UMATILLA

State of... OREGON... I hereby certify that the within instrument was filed in this office for record on the... day of... 19...

... by ... (COUNTY OFFICIAL) (DEPUTY)