


C-19

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

CENTER $\frac{1}{4}$ CORNER, SEC. 2, T3N R37E

History of original corner establishment:

NO RECORD



C-19

Description of corner evidence found:

NONE

Description of monument and accessories | established to perpetuate the original location of this corner:

SET 2" x 30" ALUMINUM PIPE WITH 2 1/2" AL. CAP, MARKED AS SHOWN ABOVE, 24" IN GROUND, FROM WHICH:

- A FIR, 12" DIAM., SCRIBED "C $\frac{1}{4}$ S2 BT" BEARS N 20 1/2° W, 21.7 FT.
- A SPRUCE, 16" DIAM., SCRIBED "C $\frac{1}{4}$ S2 BT" BEARS N 69 1/2° E, 66.2 FT.

SET A STEEL POST 3' SOUTH OF CORNER, WITH SIGN 54-4.
 PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Victor M. McLind

OREGON
 JULY 17, 1970
 VICTOR M. MCLIND
 934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By KA

No. 86-91-R

Office of... SURVEYOR ... County of... UMATILLA ...

State of... OREGON ... I hereby certify that the within instrument was filed in this office for record on the... day of... 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)