


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

CENTER 1/4 COR. SEC. 1, T3N R37E

History of original corner establishment:

No RECORD



C-23

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH A 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 24" IN GROUND, FROM WHICH:

- A SPRUCE, 8" DIAM., SCRIBED "C 1/4 S1 BT" BEARS S 37 1/2° E, 11.2 FT.
- A FIR, 12" DIAM., SCRIBED "C 1/4 S1 BT" BEARS S 34° W, 22.0 FT.

SET A STEEL POST 3 FT. SOUTH OF CORNER, WITH SIGN 54-4.
 PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE, AND SIGN 54-4 TO BACK OF TREES.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Victor McLind

OREGON
 JULY 17, 1879
 VICTOR M. McLIND
 934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By [Signature]

No. 86-96-R

Office of SURVEYOR County of UMATILLA

State of OREGON, I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)