

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 37E., W.M.

Corner Code No. C-25


Note: Monument marked as shown below

History of original corner establishment:

Corner was established by George S. Pershin under Contract No. 304 dated September 19, 1876. Original notes state:  
Set a fir post on level for 1/4 sec. cor. from which:  
A spruce, 10 ins. diam. bears N 84° E, 49 lks marked 1/4 S BT.  
A fir, 28 ins. diam. bears S 60° W 15 lks marked 1/4 S BT.

This corner was changed to apply to Section 1 only by John Kimbrell, under Contract No. 700.

In 1976, as noted in Certificate Record No. Q-1228, the fir bearing tree was recovered by J.B. Hanley and used to re-establish the corner position by reversing record bearing and distance. Certificate No. Q-1228 states:  
Set a 2 1/2" brass cap on a 2" iron pipe 3 1/2" long 6" above the ground with a 6" steel fence post 3" north with signs 54-4 and 54-2 attached.  
New bearing trees:  
A fir 12" diam. bears S 73° W 61.5 ft. dist. marked 1/4 S1 BT.



C-25

Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe protruding 4" out of the ground from which:

A 20" white fir bears S 75°W, 61.0' with healed double blaze. (Hanley)  
A 40" very rotted white fir bears S 60°W, 8.6' with axe marks visible.  
(Original bearing tree--too rotten to paint and attach signs)

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained monument by remounding with earth.

Set steel fence post South of corner and attached signs 54-2 and 54-9.

Marked 3 new bearing trees:

A 13" Englemann spruce bears S 38°W, 30.7' scribed 1/4 S1 BT.  
A 11" Englemann spruce bears N 45°W, 26.8' scribed 1/4 S1 BT.  
A 11" white fir bears N 24 1/2°W, 65.9' scribed 1/4 S1 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 1-92  
Rec'd By AK  
No. 92-02-R

☆ GPO-788-276