


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

S.W. 1/6 CORNER, SEC. 1, T3N R37E

History of original corner establishment:

No RECORD



D-22

Description of corner evidence found:

NONE

Description of monument and accessories I established to perpetuate the original location of this corner:

SET A 2" X 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 22" IN GROUND, IN A STONE MOUND, FROM WHICH:

A FIR, 6" DIAM., SCRIBED "SW 1/6 S1 BT" BEARS S 79 3/4° W, 48.5 FT.

A PINE, 7" DIAM., SCRIBED "SW 1/6 S1 BT" BEARS N 25° E, 93.5 FT.

SET A STEEL POST 3' NORTH OF CORNER, WITH SIGN 54-4.

PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGNS 54-3 ABOVE BLAZE, AND SIGNS 54-4 TO BACK OF TREES.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLind

OREGON
JULY 17, 1970
VICTOR M. McLIND
934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By KA

No. 86-98-R

Office of.....SURVEYOR..... County of UMATILLA.....

State of.....OREGON....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (COUNTY OFFICIAL) (DEPUTY)