

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by George S. Pershin under G.L.O. contract number 340 dated Sept., 26, 1879.

Surveyor General's records state:

Set a fir post on level plateau for 1/4 cor from which:

A fir 12" diam. bears N 80° E., 25 lks dist marked 1/4 S BT
A fir 11" diam. bears S 35° E., 11 lks dist marked 1/4 S BT



E-23

Description of corner evidence found:

Found a fir stump 32" diam.(sawed at 24") bears N 80° E., 16.5 ft.(25 lks) dist with scribes B T visible.

Found a depression in the ground indicating an old stump hole bears S 35° E., 7.26 ft.(11 lks) dist.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 6" above the ground with a 6' steel fence post 3' east with signs 54-4 and 54-2 attached.

new bearing trees:

A pine 7" diam. bears S 55° E., 54.0 ft. dist. marked 1/4 S 12 BT
A larch 6" diam. bears N 36° E., 54.0 ft. dist. marked 1/4 S 1 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze

Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976.....
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

