


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by George S. Pershin under G.I.O. contract number 304 dated Sept., 19, 1878.

Surveyor General's records state:

Set a basalt stone 14" x 12" x 4" on SE face of mountain in mound of stone for cor to secs 1-12-6 & 7 from which:



E-25

- A pine 10" diam. bears N 18° E., 51 lks dist marked T 3 N R 38 E S 6 BT
- A pine 18" diam. bears S 70° E., 107 lks dist marked T 3 N R 38 E S 7 BT
- A fir 14" diam. bears S 74° W., 160 lks dist marked T 3 N R 37 E S 12 BT
- No other trees

Description of corner evidence found:

A pine 32" diam. bears N 18° E., 33.66 ft. (51 lks) with a healed blaze. Found axe marks on blaze inside 9" of overgrowth. No visible scribe marks.

A pine 26" diam. bears S 70° E., 70.6 ft. (107 lks) with a partially healed blaze. No visible scribe marks.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on 2" iron pipe 31" long 10" above ground in earth and rock mound with a 6' steel fence post 4' south with sign 54-4 attached.

new bearing trees:

- A fir 7" diam. bears N 10° W., 32.0 ft. dist marked T 3 N R 37 S 1 BT
- A fir 12" diam. bears S 20° W., 61 ft. dist marked T 3 N R 37 S 12 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.

NOTE:

When this corner was set in 1878 by George S Pershin it was called the corner to sections 1,12,6 & 7, but in 1899 when John W. Kimbrell surveyed T 3 N R 38 E, he found the corner to sections 6 & 7 to be 9.65 chains north of Pershin's location. Kimbrell consequently set his corner to sections 6 & 7 and destroyed the marks on Pershin's section 6 & 7 bearing trees. Therefore, the two pine BT's are believed to be Pershin's original bearing trees.

Office of Surveyor County of Umatilla
 State of Oregon , I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976
 by
 (COUNTY OFFICIAL) (DEPUTY)

