


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-13

History of original corner establishment:

1879, George S. Pershin, U.S. Deputy Surveyor, while surveying a portion of the township under General Land Office Contract No. 340 established the corner as follows:
 Set Basalt Stone 18 X 8 X 6 on South face of bluff for cor. to Sec. 15, 16, 21 & 22
 Pine 30 in. di. brs. N. 64° E. 184 lks dist
 Fir 8 in. di. brs. S. 55° E. 194 lks dist
 Pine 16 in. di. brs. S. 30° W. 91 lks dist
 No tree near in N.W.




1900, William E. Campbell, U.S. Deputy Surveyor, while retracing the south boundary of sections 13 - 18 and completing the subdivision of the township under General Land Office Contract No. 718 described the corner as follows:
 S. 89°45' W., on a blank line, S. bdy. of sec. 15; at 79.09 chs. the temp. closing cor. of secs. 21 and 22 bears N 5 lks. dist.; and at 79.99 chs. the cor. of secs. 15 and 16, reestablished by me this day, a basalt stone 8 X 6 X 4 1/2 ins. above ground, marked and witnessed as described in the field notes of survey of subdivision returned to the surveyor general, bears N. 5 lks. dist.

1980, John P. Lee, BLM Cadastral Surveyor, described the corner as follows:
 The cor. of secs. 15 and 16 only, monumented with the original basalt stone, 18 x 8 x 6 ins., firmly set 13 ins. in the ground, mkd. with 3 notches on NE. and NW. edges, from which the remains of the original bearing trees:
 A pine, 39 ins. diam., bears N. 72 1/2° E., 212 lks. dist., with scribe marks R37 S1 B visible on partially healed blaze. (Record, N. 71° E., 209 lks.)
 At the corner point
 Set an iron post, 28 ins. long 2 1/2 ins. diam., 22 ins. in the ground, with brass cap
 from which a new bearing tree
 A pine, 21 ins. diam., bears N. 12 3/4° W. 86 lks. dist., mkd. T3N R37E S16 BT.
 Deposit corner stone alongside iron post.

Description of corner evidence found:

Found a 2 1/2" iron pipe, with 3 1/4" BLM brass cap, projecting 6" out of the ground, marked as shown, from which:
 38" Ponderosa Pine, bears N. 70 1/2° E., 139.9 feet, with scribing visible on chopped open blaze (Lee's Record N. 72 1/2° E.).
 26" Ponderosa Pine, bears N. 14° W., 56.8 feet, with healed blaze (Lee's Record N. 12 3/4° W.).



Description of monument and accessories established to perpetuate the original location of this corner:

New References:
 6" Ponderosa Pine, bears N. 69° W., 40.6 feet scribed "T3N R37E S16" "BT" on double blaze with 3/4" brass washer "RLS 2308" nailed to the lower blaze.
 RM, 5/8" by 24" rebar with a 1 1/4" diameter red plastic cap stamped "UMATILLA N.F.", set 22" in the ground, bears S. 89°48' W., 45.75 feet.

DATUM: NAD83(1991)
 STATE PLANE COORDINATES: Oregon North Zone in International Feet

| | | | |
|-----------------------|-----------------------|-------------|-------------|
| Latitude | Longitude | Northing(y) | Easting(x) |
| 45°43'48.64640" North | 118°11'27.23820" West | 760740.467 | 8791677.176 |

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

David A. Schlaich

OREGON
 JULY 16, 1987
 DAVID A. SCHLAICH
 2308

RENEWAL DATE: 06/30/2006

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 20.....
 by.....
 (COUNTY OFFICIAL) (DEPUTY)