


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories I established to perpetuate the original location of this corner:

At a point on the East line of section 36 and on the Wilderness Boundary line, 778.31 feet north of the E 1/4 corner, at an Elevation of 4240 feet, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which:

New Bearing Tree and Bearing Object;

A 5 inch diameter Douglas Fir bears N80°E, 26.50 feet marked X BT  
A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears N85°W, 18.25 feet.

Attached Bearing Tree and Land Survey Monument signs to the bearing tree.

Set a steel fencepost approximately 5 feet Southerly with Land Survey Monument and Wilderness Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on Sept. 10, 1992.

Witness: Jim Bennett



I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by ..... (DEPUTY)  
(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 10-92  
Rec'd By KF  
No. 92-118-R

\*GPO-591-971, 1988