


History of original corner establishment:

The original corner was established by William E. Campbell on August 15, 1900, under joint GLO contract number 718, as follows:

Set a basalt stone, 20" x 10" x 4", marked with 2 notches on the south and 3 notches on the east edges, from which:

- A 22" pine bears N51°30'E, 62 links (40.92 feet).
- A 20" fir bears S21°45'E, 190 links (125.40 feet).
- A 14" fir bears S45°W, 8 links (5.28 feet).
- A 30" pine bears N60°30'W, 99 links (65.34 feet).



R-13

Description of corner evidence found:

The corner stone is gone. Probably rolled down the steep hillside. The decayed root crown of a Ponderosa Pine, no marks remaining, bears N57°E, 41.8 feet. The decayed root crown of a fir, which is east of the South Fork of the Umatilla River, bears S19°E, 125.4 feet. No marks remaining. The decayed root crown of a fir, with fragmentary scribing lying down slope, bears S45°W, 5.28 feet. The original 30" pine is a windthrown Ponderosa Pine lying on the blazed face. I open to scribes "T3N" and "S21". Root hole bears N60°30'W, 65.34 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the accessories, I set a 2 1/2" x 30" aluminum pipe, with a 3 1/4" aluminum cap attached, 30" into the ground with the cap flush. The cap is marked as shown in the diagram above, from which:

- A 16" Ponderosa Pine scribed "T3N R37E S22 BT" on double blazes bears N38°30'E, 78.4 feet.
- A 5/8" x 24" iron rod, set 20" into the ground on top of a small rock point, with a 3/4" brass washer marked "PLS 1636" attached at ground level, bears S85°30'E, 26.5 feet.
- A 5/8" x 24" iron rod, set 23" into the ground on top of a small rock point, with a 1 1/2" aluminum cap attached marked "USDA-FS" "PLS 1636", bears S68°15'W, 49.6 feet.
- A 22" Douglas-fir scribed "T3N R37E S21 BT" on double blazes bears N27°30'W, 78.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 9, 1997. Magnetic declination: 20°E.



Office of _____ County of _____
State of _____, I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____

_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 10-97

Rec'd By KK

No. 97-192-R