


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**History of original corner establishment:**

Corner originally established by George S. Pershin under GLO contract number 304, dated September 19, 1878. Surveyor General record states:

Set a basalt stone 16 X 8 X 7 on SW hill, from which;  
Fir 8 in diam brs N10°E, 60 lks dist  
Fir 20 in diam brs S24°E, 99 lks dist  
Fir 36 in diam brs S38°W, 66 lks dist  
Fir 18 in diam brs N68°W, 74 lks dist  
Corner found by William E. Campbell under GLO contract number 718, dated May 1, 1900. Surveyor General record states:  
In retracing the S Bdy of sec 35, I discover it to be defective.  
Set basalt stone 15x15x4 ins 10 ins in the ground for corner to sect 35 and 36 marked with 1 notch on the E and 5 notches W.  
From which:  
A fir 10 ins diam bears N14°E, 52 lks dist marked T3N R37E S36 BT  
A fir 18 ins diam bears N51°W, 132 lks dist marked T3S R37E S35 BT  
The old cor of sec 35 and 36 bears west 1 chain 25 lks dist  
I destroy all traces of this old sec cor.



No record of subsequent monumentation found in Umatilla County survey records.

Found stone 16 x 14 x 4, 9" in the ground, marked with 5 notches west and 1 notch east.

Found a 18 inch diameter Douglas Fir N14°E, 52 lks. dead and down scribes visable.  
Found a 20 inch diam Douglas Fir N51°W, 87 feet, down on the face.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

In place of found stone, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 26 inches in the ground, from which:

New Bearing Trees and Bearing Object;  
A 15 inch Douglas Fir bears N26°E, 45.94 ft. marked T3N R37E S36 BT  
A 5/8"x18" iron pin with plastic cap marked BGA SURVEY MARKER bears North, 4.71 feet  
A 5/8"x18" iron pin with plastic cap marked BGA SURVEY MARKER bears East, 7.60 feet  
A 14 inch diameter Douglas Fir bears N68°W, 63.90 feet marked T3N R37E S35 BT  
Attached Bearing Tree and Land Survey Monument signs to the bearing trees.  
Buried stone west and alongside pipe.

Set a steel fencepost approximately 5 feet North with Land Survey Monument and wilderness boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 30, 1991.

Witnesses: Jeff Petersen and Jeff Bennett



I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 10-92  
Rec'd By KR  
No. 92-118-R