

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

Tract or
Survey No. **N.F. UMATILLA** Cor.
No. **AP-676**

T. 3 N. R. 38 E.

R.D. WALLA-WALLA County **UMATILLA**

Merid. Willamette

N.F. Umatilla State **Oregon**

CORNER DIAGRAM

**N.F.
UMATILLA
WILD.**



AP-676

DESCRIBE CORNER MONUMENT FOUND
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,620,865.85'

Y: 754,034.47'

Datum: NAD 1927

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
From the junction of F.S. roads 3100 and 3100-360, travel northwesterly on road 3100-360 approx. 2.0 miles. From this point descend to the west approx. 400 feet to the corner which is located at the head of a small draw at an elevation of 5000 feet.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquartes

S.O.

Date

10/1996

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set on the 5000 foot contour in a small draw a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, flush with the ground, stamped "NFU WILDERNESS AP-676 RLS 2308 1996".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

10" White Fir, N. 79 1/2° E., 10.6 feet, mkd. "WB/676" "BT".

8" White Fir, S. 27° E., 21.1 feet, mkd. "WB/676" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich Title Land Surveyor Date 10/1996 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No _____ Filed At: _____ Date _____

REMARKS

Index File No.

T. **3 N.**

R. **38 E.**

M. **Willamette**

Tract or Survey No.

N.F. Umatilla Wild.

Cor. **AP-676**