


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

North Fork Umatilla Wilderness
AP-733

History of original corner establishment:
None



Description of corner evidence found:
None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 5/8" by 30" rebar, with 3 1/4" aluminum cap, 29" in the ground, marked as shown, from which:
 5" Douglas Fir bears S. 66° E., 61.8 feet, scribed "WB/733" "BT" on double blaze with 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze.
 5" Douglas Fir bears S. 22 1/2° E., 53.6 feet, scribed "WB/733" "BT" on double blaze with 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze.



DATUM: NAD83(CORS96) (EPOCH:2002.0000)
 STATE PLANE COORDINATES: Oregon North Zone in International Feet

Latitude	Longitude	Northing(y)	Easting(x)
45°43'01.33931" North	118°05'40.02387" West	756669.565	8816438.652

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David A. Schlaich

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2006

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 20.....
 by.....
 (COUNTY OFFICIAL) (DEPUTY)