

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

Tract or
Survey No.

**N.F. Umatilla
Wilderness**


Cor.
No. **AP-777**

T. 3 N. R. 38 E.
Merid. Willamette

R.D. Walla-Walla
N.F. Umatilla

County Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
NONE

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
From the junction of F.S. road 3100 and abandoned road 3100-287 walk northwesterly on the abandoned road (now a trail) approx. 2900 feet. From this point the corner is located approx. 100 feet west of the road.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 6,616,117.42'
Y: 751,307.62'
Datum: NAD 1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/1996

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set at a point 100 feet westerly of and perpendicular to abandoned road 3100-287, a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, 23" in the ground, stamped "NFU WILDERNESS AP-777 RLS 2308 1996".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

22" bole of a double bole Douglas Fir, S. 4 1/2° E., 82.9 feet, scribed "WB/777" "BT".
23" White Fir, S. 25 1/2° W., 79.9 feet, scribed "WB/777" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich Title Land Surveyor Date 10/1996 State Registration No. _____
or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS