

USDA-FOREST SERVICE

Index

File No.

T. 3 N. R. 38 E.
Merid. WILLAMETTE

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)


R.D. WALLA-WALLA
N.F. UMATILLA

County UMATILLA
State OREGON

Tract or
Survey No. NF UMATILLA

Cor.
No. AP-389

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner is located in a small draw at an elevation of 5000 feet.

PLANE COORDINATE POSITION

State: OREGON Zone: NORTH

X: 2,688,612.911 meters

Y: 235,567.368 meters

Datum: NAD83(1991)

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09/1994

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, mkd. "NFU WILDERNESS AP-389 ELEV 5000 RLS 2308 1994"

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

22" Douglas Fir, N. 57 1/4° E., 5.4 ft., mkd. "WB/389""BT".
21" Douglas Fir, S. 20 1/4° W., 8.3 ft., mkd. "WB/389""BT".

The BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By **D. Schlaich** Title **Land Surveyor** Date **09/1994** State Registration No. or Agency

Certified Cor. Record Prepared ? **NO** Filed At: Date

REMARKS

Index File No. T. **3 N.** R. **38 E.** M. **W.M.** Tract or Survey No. **NF UMATILLA** Cor. **AP-389**