


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-05  
(200300)

History of original corner establishment:

1899, John W. Kimbrell. U.S. Deputy surveyor, while surveying the township under General Land Office Contract No. 700 established the corner as follows:  
Set fir post 3 ft long 3 ins Sq 24 ins in the ground for Cor of Secs 19-20-29 and 30 marked T3N S20 on NE R38E S29 on SE S30 on SW and S19 on NW faces with 2 notches on S and 5 notches on S edges, from which:  
a Willow 3 ins diam bears N68°E 17 lks dist marked T3NR38ES20B.T.  
a Willow 3 ins diam bears S2°E 44 lks dist marked T3NR38ES29B.T.  
a Tamarack 9 ins diam bears S1°W 175 lks dist marked T3NR38ES30B.T.  
a Willow 3 ins diam bears N69°W 41 lks dist marked T3NR38ES19B.T.  
NOTE: John Kimbrell's 1899 survey was rejected by the General Land Office.



1903, John W. Kimbrell. U.S. Deputy surveyor, while resurveying the township under General Land Office Contract No. 700 established the corner as follows:  
Set basalt stone 18 X 9 X 6 ins, 12 ins in the ground for cor of secs 19, 20, 29 and 30 marked with 2 notches on S 5 notches on E sides, and raised a mound of stone 2 ft. base 1 1/2 ft high W of cor, pits impracticable.  
From this cor the old sec cor, a post marked and witnessed bears N 595 lks dist. I destroy cor & marks on bearing trees.

Description of corner evidence found:

Found a basalt stone 14 inches by 10 inches by 5 inches with 5 groves on East face of the stone.

Description of monument and accessories I established to perpetuate the original location of this corner:

I set in place of the stone a 2 1/2 inch diameter by 30 inch long aluminum pipe, with a 3 1/4 inch diameter aluminum cap, 22 inches in the ground (partially buried stone on North side of monument), marked as shown, from which:



New BT's:

- 15 inch diameter Fir bears N. 85 1/2° E., 42.9 feet, scribed "T3N R38E S20" "BT" on double blaze.
- 11 inch diameter Western Larch bears S. 20° E., 14.9 feet, scribed "T3N R38E S29" "BT" on double blaze.
- 10 inch diameter Lodgepole Pine bears S. 43 1/2° W., 10.6 feet, scribed "T3N R38E S30" "BT" on double blaze.
- 24 inch diameter Western Larch bears N. 42 1/2° W., 56.9 feet, scribed "T3N R38E S19" "BT" on double blaze.

The new bearing trees have a 3/4 inch diameter brass washer stamped "RLS 2308" nailed to the lower blaze near the "BT" scribing.

Work Performed By: David A. Schlaich (RLS 2308)  
Witnessed By: Levi D. Hamby  
Equipment: Warren-Knight Surveyors Compass and 75 foot steel tape  
Magnetic Declination 19' east  
Date: July 3, 2000

REGISTERED PROFESSIONAL LAND SURVEYOR

*David A. Schlaich*

OREGON  
JULY 16, 1987  
DAVID A. SCHLAICH  
2308

RENEWAL DATE: 06/30/2002

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by.....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Wasilla County Surveyor  
Date 8-00  
Rec'd By KR  
No. 00-169-R