


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-07

History of original corner establishment:

1899, John W. Kimbrell. U.S. Deputy surveyor, while surveying the township under General Land Office Contract No. 700 established the corner as follows: Set fir post 3 ft long 3 ins Sq 24 ins in the ground for 1/4 Sec Cor marked 1/4 S20 on N face 29 on S face from which a fir 10 ins diam bears N18°W 30 lks dist marked 1/4S20BT. a fir 28 ins diam bears S35°E 4 lks dist marked 1/4S29B.T. NOTE: The General Land Office rejected John Kimbrell's 1899 survey.



R.B.

1903, John W. Kimbrell. U.S. Deputy surveyor, while resurveying the township under General Land Office Contract No. 700 established the corner as follows: Set granite stone 16 X 12 X 6 ins 10 ins in the ground for 1/4 sec cor, marked 1/4 on N face from which a fir 22 ins diam bears S56°E 29 lks dist marked 1/4S29BT. a fir 22 ins diam bears N71°W 39 lks dist marked 1/4S20BT. From this cor. the old 1/4 sec cor, a post marked and witnessed bears N1 1/2°W 605 lks dist. I destroy post cor. and marks on bearing trees.

Description of corner evidence found:

Found stone 14" X 12" X 6" with no marks visible set 2" in the ground, from which: 32" Douglas Fir bears S. 50° E., 19.1 feet, with healed blaze (record S 56° E). 27" Douglas Fir bears N. 71° W., 23.5 feet, with axe marks and scribing visible on almost completely healed blaze (record 39 lks = 25.7 feet).

Description of monument and accessories I established to perpetuate the original location of this corner:

I replace the stone with a 2 1/2" by 28" aluminum pipe, with 3 1/4" aluminum cap, set 21" in the ground and bury the stone on the south side of the monument which is marked as shown. Marked new bearing trees: 11" Douglas Fir bears N. 66 1/4° E., 24.3 feet, scribed "1/4S20" "BT" on double blaze with 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze. 18" Douglas Fir bears N. 12 1/2° W., 31.2 feet, scribed "1/4S20" "BT" on double blaze with 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze.



DATUM: NAD83(CORS96) (EPOCH:2002.0000) STATE PLANE COORDINATES: Oregon North Zone in International Feet

Latitude 45°43'02.77890" North Longitude 118°05'16.28928" West Northing(y) 756865.513 Easting(x) 8818117.532

REGISTERED PROFESSIONAL LAND SURVEYOR

David A Schlaich

OREGON JULY 16, 1987 DAVID A. SCHLAICH 2308

RENEWAL DATE: 06/30/2008

Office of..... County of..... State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20..... by..... (COUNTY OFFICIAL) (DEPUTY)