


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 1
DIAGRAM

History of original corner establishment:

The original corner was established by George Williams on September 19, 1872, under GLO contract No. 176, as follows:

Set a stone, 18" x 10" x 6", for 1/4 section corner.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 16" x 8" x 6" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 18" iron rod set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N60° 30' E, 119.8 feet.

A 5/8" x 18" iron rod set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S45° E, 112.2 feet.

A 5/8" x 18" iron rod set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S68° 30' W, 111.7 feet.

A 5/8" x 18" iron rod set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N37° 30' W, 107.5 feet.

This corner marks a point on the Morrow - Umatilla County line.

I hereby certify the above corner point was perpetuated as hereon described on February 15, 2005. Magnetic declination set in compass: 15° E.
NAD '83 UTM Zone 11 position: 5022461N, 331866E (plus or minus two meters).

A handwritten signature "Dennis L. Gaylord" is written over a rectangular seal. The seal contains the text: REGISTERED PROFESSIONAL LAND SURVEYOR, OREGON, JULY 14, 1970, DENNIS L. GAYLORD, 1636.

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 2-05
 Rec'd by KK
 No. 05-49-R