


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 25
DIAGRAM

History of original corner establishment:

The original corner was established by George Williams on September 28, 1872, under GLO contract No 176, as follows:

Set a stone, 25" x 8" x 6", on north side of hill for the corner to sections 12, 13, 7 and 18, from which:



A high round top iron rock butte bears N19° 30' E about 35 chains distance.

Original corner evidence recovered:

Found the original corner stone solidly set in the ground in a mound of stones. The original corner stone is 26" x 6" x 6" and is plainly marked with two notches on the north edge and four notches on the south edge, from which:

I find the rounded top of a butte bears N18° E, about 40 chains, or one-half mile distant.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 18" into the ground to bedrock. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S7", attached at ground level, bears N67° E, 83.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 18", attached at ground level, bears S27° E, 90.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 13", attached at ground level, bears S38° 30' W, 90.8 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 12", attached at ground level, bears N19° W, 104.3 feet.

This corner marks a point on the Morrow - Umatilla County line.

I hereby certify the above corner point was perpetuated as hereon described on February 8, 2005. Magnetic declination set in compass: 14° E.
NAD '83 UTM Zone 11 position: 5020035N, 331769E (plus or minus two meters).


Dennis L. Gaylord


Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 2-05
 Rec'd by KK
 No. 05-27-R