


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 23
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, Deputy, on October 20, 1871, under GLO contract No. 154, as follows:

Set a stone, 22" x 10" x 6", for the 1/4 section corner to sections 36 and 1.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 22" x 12" x 8" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 20" into the ground. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", wired to the rod at ground level, bears N35° 30' E, 92.6 feet.

A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", wired to the rod at ground level, bears S46° E, 116.7 feet.

The most northerly leg of a 30' high steel tower, with a 3/4" brass washer, marked "PLS 1636 SW", wired to the leg one foot above the ground, bears S37° 30' W, 135.5 feet.

A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", wired to the rod at ground level, bears N41° W, 141.0 feet.

A barbed wire fence, projecting east and west, bears south, 3.0 feet.

I wire a "Witness Post" sign to a steel fence post S66° W, 7.5 feet from the corner.

I hereby certify the above corner point was perpetuated as hereon described on February 6, 2004. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5022913N, 340842E (plus or minus two meters).

REGISTERED PROFESSIONAL LAND SURVEYOR
Dennis L. Gaylord
OREGON JULY 14, 1978 DENNIS L. GAYLORD 1636

RECEIVED BY
Umatilla County Surveyor
Date 2-04
Rec'd By KK
No. 04-39-R

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: