


History of original corner establishment:

The original corner was established by George S. Pershin on May 2, 1879, under contract number 319, as follows:

Set a basalt stone, 18" x 10" x 8" on west side of ridge for the 1/4 section corner.



Description of corner evidence found:

I find the original corner stone set solidly in place and plainly marked "1/4" on the east face. The stone is 18" x 11" x 8" and is set 12" into the ground.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the exact point occupied by the corner stone, I set a 1 1/2" x 30" iron pipe 26" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone alongside the north side of the pipe, from which:

A 3/4" x 32" aluminum rod set 30" into the ground with a 5/8" brass washer attached at ground level, marked "PLS 1636 S1 NE", bears N39°E, 44.1 feet.

A 3/4" x 36" aluminum rod set 34" into the ground with a 5/8" brass washer attached at ground level, marked "PLS 1636 S1 SE", and an unmarked blue plastic cap, bears S43°E, 52.4 feet.

A basalt outcrop, 18" high by 10' long with chisel marks "+ 2" on the northeast face near the top, bears S71°W, 124.6 feet. I build a mound of stones on top of the outcrop above the chisel marks.

A 3/4" x 36" aluminum rod set 34" into the ground with a 5/8" brass washer attached at ground level, marked "PLS 1636 S2", bears N39°W, 60.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on November 2, 1996. Magnetic declination: 20°E.

REGISTERED PROFESSIONAL LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 11 1978
DENNIS L. GAYLORD
1636

Office of COUNTY SURVEYOR County of UMATILLA
State of OREGON, I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

Renewed 6/30/97

..... by
(COUNTY OFFICIAL) RECEIVED BY

Umatilla County Surveyor
Date 11-96
Rec'd by KK
No. 96-187-R