


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 25
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin under GLO contract No. 304 dated September 19, 1878, as follows:



Set a stone, 24" x 14" x 12", on a north hillside for the quarter section corner.

Corner evidence recovered:

Found the original corner stone solidly set on the east edge of a small mound of stones. The corner stone is 23" x 17" x 12" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 26" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe, from which:

- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N70°30'E, 72.9 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S43°30'E, 88.2 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S47°30'W, 67.7 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N17°15'W, 66.2 feet.

This is a quarter section corner of minimum control. It controls the location of the range line and the subdivision of section one, only.

I hereby certify the above corner point was perpetuated as hereon described on August 27, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14 1978
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on December 31, 1998.

RECEIVED BY

Umatilla County Surveyor

Date 12-98

Rec'd By KK

No. 98-250-R