


History of original corner establishment:

Original corner established by George S. Pershin on May 2, 1879, under contract No. 319, as follows:

Set a basalt stone 17" x 10" x 8" in creek bottom for 1/4 section corner, from which:

- A 11" fir bears N42°E, 27 links (17.82 feet).
- A 12" fir bears S76°W, 58 links (38.28 feet).



Description of corner evidence found:

A dilligent search for the stone described above as the corner monument was unsuccessful. An error is obvious in measurements made by Pershin to the bearing trees. The scribed blazes on the original bearing trees are facing a 34" sawn, unmarked Douglas-fir stump, which I determine was a corner tree, from which:

A 27" sawn Douglas-fir stump with a healed blaze bears S84°W, 48.1 feet. I open the blaze to reveal scribes "S BT".

A 28" sawn Douglas-fir stump with a healed blaze bears N41°E, 15.8 feet. I open the blaze to reveal scribes "1/4 S BT".

Description of monument and accessories I established to perpetuate the original location of this corner:

I drive a 5/8" x 36" iron rod, 30" into the center of the original corner tree stump. The rod has a 1 1/2" aluminum cap attached which is marked as shown in the diagram above, from which:

- A 11" Alder, scribed "1/4 S1 BT" through the bark, bears N6°E, 36.6 feet.
- A 5" Alder, scribed "1/4 S12 BT" through the bark, bears S53°E, 13.3 feet.
- A 14" White Fir, scribed "1/4 S12 BT" on double blazes, bears S73°30'W, 60.4 feet.
- A 22" Ponderosa Pine, scribed "1/4 S1 BT" on double blazes, bears N65°30'W, 82.7 feet.

The four new bearing trees have a 5/8" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Tree" sign nailed above the scribing. The bearing tree to the northwest also has a "Witness Post" sign nailed to the back of the tree. The original bearing tree remains have a "Bearing Tree" sign nailed to them.

I hereby certify the above corner point was perpetuated as hereon described on May 19, 1996. Magnetic declination: 20°E.



Office of County Surveyor County of UMATILLA
 State of OREGON, I hereby certify that the within instrument was filed in this office
 for record on the 27 day of May, 1996
David H. K. by _____
 (COUNTY OFFICIAL) (DEPUTY)

Renewed
6/30/97

E-23

RECEIVED BY
 Umatilla County Surveyor
 Date 5-96
 Book h.k.
 No. 96-73-R