


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 13
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 8, 1879, under GLO contract No. 319, as follows:

Set basalt stone 18" x 14" x 6" on west face of ridge for corner to sections 9, 10, 15 and 16. Drove stake and raised mounds of stone around stone and stake in lieu of pits.



Corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 24" x 17" x 7" and is plainly marked with three notches on the east edge and two notches on the north edge. A mound of stones bears S35°E, 4.0 feet. The stake called for in the original notes is gone.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 26" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S10", attached at ground level, bears N38°30'E, 80.0 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S15", attached at ground level, bears S50°E, 77.5 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S16", attached at ground level, bears S47°W, 136.4 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S9", attached at ground level, bears N49°W, 94.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 7, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 16, 1956
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 6-98
Rec'd By KL
No. 98-109-L