


History of original corner establishment:

Original corner set by George S. Pershin on May 1, 1879, under contract number 319, as follows:

Set a basalt stone 14" x 10" x 5" on a west mountain side, from which:

- A 10" Pine bears N38°E, 52 links (34.32 feet).
- A 24" Pine bears S70°E, 38 links (25.08 feet).
- A 13" Pine bears S28°W, 89 links (58.74 feet).
- A 16" Pine bears N22°W, 138 links (91.08 feet).



Description of corner evidence found:

A scattered mound of stones at the corner. The corner stone has rolled down hill, disturbed by logging activities. The corner stone is 16" x 10" x 6" and is marked with 2 notches on one edge. From the corner point, as determined from the accessories:

- A down and decayed Ponderosa Pine with scribes, "T3S R31E S13 BT", visible. The broken stump bears S70°E, 25.1 feet.
- A decayed and burnt stump bears S28°W, 58.7 feet. No marks remain.
- A decayed stump bears N38°E, 34.3 feet. No marks remain.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the original bearing tree remains, I set a 1" x 30" iron pipe 27" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram, above. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe, from which:

- A 16" Douglas-fir, scribed "T3S R31E S11 BT", bears N27°W, 30.0 feet.
- A 8" Western Larch, scribed "T3S R31E S12 BT", bears N86°E, 13.8 feet.
- A 13" Douglas-fir, scribed "T3S R31E S13 BT", bears S25°E, 33.0 feet.
- A 12" Ponderosa Pine, scribed "T3S R31E S14 BT", bears S32°W, 39.4 feet.

All new bearing trees are scribed on double blazes and have a 5/8" brass washer, marked "PLS 1636", nailed flush to the lower blaze, and have a "Bearing Tree" sign nailed above the blazes.

I hereby certify the above corner point was perpetuated as hereon described on April 28, 1996. Magnetic declination: 20°E.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Dennis L. Gaylord

OREGON
DENNIS L. GAYLORD
1636

RENENS 6/30/97

Office of COUNTY SURVEYOR County of UMATILLA
 State of OREGON, I hereby certify that the within instrument was filed in this office
 for record on the 10 day of May, 1996
David H. Klein by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor
 Date 5-96
 Rec'd by KK
 No. 96-69-A